



Gokhale Institute of Politics and Economics

(Founded by Rao Bahadur R.R. Kale, Satara)
(Deemed to be University u/s 3 of the UGC Act, 1956)
846, Shivajinagar, B.M.C.C. Road
PUNE - 411 004 (INDIA)

Ref No. 28.3.5/ 1014/2026

Date: 24/09/2026

REQUEST FOR QUOTATIONS (RFQ)

PROPOSED RENOVATION OF THE TOILET OF THE KALE HALL (Near Stage) IN THE ACADEMIC CAMPUS OF GOKHALE INSTITUTE OF POLITICS & ECONOMICS, PUNE-411004.

Gokhale Institute of Politics and Economics intends to renovate the toilet of the Kale Hall (near stage) for its utilization with waterproofing, plumbing sanitary work, new EWC & wash basin fixing, flooring, dado etc. complete as per site in the Academic campus.

Sealed quotations/proposals are hereby invited from experienced agencies/contractors for carrying out the above mentioned civil works. The details of the work are specified in the attached Bill of Quantities (BOQ)/Work.

Interested agencies or their authorized representatives may visit the site to inspect the work and assess the scope of maintenance activities during the period **24th Sept 2026 to 28th Sept 2026**, between **10:00 a.m. and 6:00 p.m.**

The quotations to be submitted on or before **28th Sept 2026** between **10.00 am and 6.00 pm** as per attached format.

Please contact Er. Deepak Ganbavale (M.No.9422043759) for more details.

Note:

- 1) BOQ / Format for Quotation is attached separately with the letter.
- 2) Quotations should be submitted as per attached format only & in one sealed envelope.



Kedarpikar
Mr. Kedār Tapikar
Administrative Officer

**QUOTATION FOR THE RENOVATION OF TOILET OF KALE HALL (NEAR STAGE),
LIBRARY BUILDING IN THE ACADEMIC CAMPUS, GIPE.**

Sr. No.	Description of Item	Qty.	Unit	Rate	Amount
A	Waterproofing, Flooring etc.				
1	Removing door/window frame & shutter & shifting at located place within premises complete	3.00	Nos		
2	Removing ceramic tile floor & dado tile & shifting outside the site premises complete	17.72	Sqm		
3	Providing internal wall cement plaster 6mm thick in single coat in cement mortar 1:4 applying chemical bonding agent before plaster to wall surface for preparation of dado tile fixing etc complete.	15.50	Sqm		
3	Providing and making water proofing of chemical type to the floor slab etc complete	6.50	Sqm		
4	Providing and laying matt finish ceramic tiles of approved quality 60cm x 60cm for flooring in required position laid on a bed of 1:4 cement mortar including cement float, filling joint with white / colour cement slurry cleaning curing complete. (Basic rate of tile -Rs.550/sqm)	3.50	sqm		
5	Providing and laying ceramic tiles having size 30 cm. x 60 cm. conforming to corresponding I.S. for dado and skirting in required position with readymade adhesive mortar of approved quality on plaster of 1:2 cement mortar including joint filling with white/ colour cement slurry cleaning curing etc. complete..(Basic rate of tile -Rs.550/sqm)	15.50	Sqm.		
B	Doors & Windows				
7	Providing and fixing Window granite Cill with chamfered edge fixed on a bed of CM 1:4, including cement float, filling joints with slurry, curing, edge polishing and edge chamfering, cleaning etc. and width upto 500 mm	3.60	Rmt		
8	P/F solid PVC door (Double door) with door fittings etc complete.	1.00	No		
9	P/F Al louvered window: Aluminium black power coated frame with louvers, with 4 mm glass with Exhaust fan compartment	1.00	No		
10	Providing and applying acrylic emulsion painting to walls and ceilings	10.00	Sqm		
C	Plumbing work				
11	P/F 50 mm dia. PVC soil pipe (B class) with necessary fitting	5.00	Rmt		
12	P/F 75 mm dia. PVC soil pipe (B class) with necessary fitting with required mullah work on exterior wall	30.00	Rmt		
13	P/F 110 mm dia. PVC soil pipe (B class)with necessary fitting with required zullah work on exterior wall	30.00	Rmt		

14	Providing and fixing on walls/ ceiling/ floor concealed 15 mm dia. CPVC pipe with necessary fittings, finishing the same with rich mortar portion etc. complete.	5.00	Rmt		
15	Providing and fixing on walls/ ceiling/ floor concealed 20 mm dia. CPVC pipe with necessary fittings, finishing the same with rich mortar portion etc. complete.	15.00	Rmt		
16	Providing and making core cutting for commode outlet ,fixing the outlet arrangement etc complete	1.00	Job		
17	Providing and fixing 10 cm PVC nahani trap with grating etc. complete.	1.00	No		
18	Drainage chamber 600mm x 900 mm with cover, with required 150 mm dia SWR pipe (3.00 m length)	1.00	No		
D	Sanitary fittings work				
19	Providing and fixing one piece commode with soft closing seat cover etc. complete with toway cock, flushing tank e	1.00	No		
20	Providing and fixing best quality basin etc. complete with necessary fittings i.e. stope cock, pillar cock, down take pipe.	1.00	No		
21	Providing and fixing hand spray ,cable, holder set	1.00	No		
22	Providing and fixing good Basin cock	1.00	No		
23	Providing and fixing Mirror with aluminium frame	1.00	No		
24	Providing and fixing good quality Bib cock	1.00	No		
25	Providing and fixing good quality angle stop cock	2.00	No		
26	Providing & Fixing Soap dispenser chromium plated as directed by authority	1.00	No		
27	Contingencies (10%)				
	TOTAL (A+B+C+D)				-

Note: Please site visit for more details.

- : Mention the related make of the material /fittings.
- : The execution of items as per SSR specification of the related items.
- : No escalation, no advance for the work.
- : Final bill will be after Institute's inspection & certification.
- : No extra claim will be accepted than the approved tender amount.